

# Environmental

## Henham Footbridge, Latitude Festival



## 49m wide permanent bridge in only 21 days

**Client:** Festival Republic (on behalf of Latitude Music Festival)

- The brief was to replace the existing floating bridge with a permanent structure.
- 12 helical piles designed to 8m were used.
- The structure is 49m long by 12m wide.
- The main structure was a steel frame and attached on top of the piles.
- Installation took 21 days.



7-14 Smallford Works, Smallford Lane  
St. Albans, Hertfordshire, AL4 0SA  
[www.screwfast.com](http://www.screwfast.com)

Tel: 01727 821 282 Email: [info@screwfast.com](mailto:info@screwfast.com)



THE PROVEN LEADERS IN HELICAL PILE FOUNDATIONS